

Document C — Technical Passage and Raw Notes

Exercise 2, Round 3 (Transform). Fictional. Meridian Technical Services.

C1 — Technical passage

Rewrite this twice: once for a general audience with no engineering background, and once for a board audience in three sentences (schedule and cost implications only).

Extract from Examination Report HP-EX-0441, section 6.2 — Wall Thickness Findings

Ultrasonic thickness measurement was performed at the lower circumferential weld of vessels HP-A-118 and HP-A-141 using a 5 MHz dual-element probe on a 50 mm grid, with supplementary readings at 25 mm spacing where the initial grid indicated local variation. Couplant was applied throughout and surface preparation was to Sa 2½ where the existing coating precluded direct contact.

Nominal wall thickness at this location is 14.2 mm with a design minimum of 11.8 mm established by the original design calculation and unchanged by the revised standard. Measured values on HP-A-118 ranged from 10.4 mm to 13.9 mm across 46 grid points, with 7 points falling below the design minimum and a minimum recorded value of 10.4 mm at grid reference D4. HP-A-141 exhibited a comparable distribution, with 5 points below the design minimum and a minimum recorded value of 10.9 mm at grid reference C4.

In both cases the sub-minimum readings cluster on the lower quadrant within 200 mm of the weld toe, in a pattern consistent with preferential corrosion at a location of periodic condensate retention rather than with a manufacturing deficiency. The morphology observed on visual examination following coating removal supports this interpretation. The rate of loss cannot be established from a single examination; the previous recorded examination of either unit was in 2018 and the records for that examination consist of a scanned handwritten summary without recorded measurement values.

Both units have been reported under the immediate notification provisions of the contract and removed from service pending client determination. Continued service at reduced operating pressure may be technically supportable but is outside the scope of this report and would require a fitness-for-service assessment to the applicable standard.

Vessels HP-A-118 and HP-A-141 originate from manufacturing batch 1997-K, of which 21 units are present in the examination population. Four further units from this batch have been examined and cleared without adverse finding. The remaining 15 units have not yet been examined.

C2 — Raw notes

Turn these into a table with columns: **Item | Owner | Due | Status | Risk if it slips**

The notes do not contain all of that. Watch carefully what the model does with the gaps.

Programme office scratch notes — Tuesday catch-up

- variation request from 2 May still no answer. Chased twice. R. Vance chasing again this week, wants an answer before the 15th
 - batch 1997-K — 15 units outstanding. Need client direction on resequencing. Sam raised it at the gate review, no response yet
 - third team option dies on 15 July, mobilisation lead time. Decision needed before then, no owner assigned to actually get the decision
 - fatigue assessment for extended working — needs doing before we can even offer that option. Priya said she'd look at it
 - Site C mobilisation 8 July. Documentation reconciliation not started. Same problem as A and B expected
 - three unaccounted vessels — client has not come back. Been six weeks
 - lead examiner for the batch work is single point of failure. Nobody has looked at cover. Discussed three times now
 - invoicing current, nothing to do
 - gate review actions both closed, confirmed Friday
 - someone needs to update the risk register with the batch issue, it's still showing as medium impact from before we found 118 and 141
-

End of document.